

Smith and Nephew

Dem-master were awarded the project following a competitive tendering process. Working closely with Smith and Nephew Medical Ltd own in-house safety and engineering team Dem-master managed to demolish a significant part of a redundant manufacturing plant without impacting on the 24 hour operations of the new manufacturing facility. After separating the building link bridges and carrying out all re-cladding, the site was isolated in order to minimise disruption.



All concrete was crushed and used to form a sub-base. The 32 week programme included the removal of all asbestos containing materials. Additional works were carried out for the client working to the original programme this involved the removal of a petrol recovery plant. Our engineers marked all equipment and P&ID's, following careful dismantling the plant was exported overseas for re-use.

Dem-master arranged all packaging, transportation and export documentation to final destination to allow the complete plant to be re-used.

Client : Smith and Nephew
Address : 101 Hessle Road, Hull , HU3 2BN
Tel: 01482 222200